

本 工 事 数 量 総 括 表	
-----------------	--

[illegible]

土工配分表

〈 本 工 事 〉

掘 削

掘削工（土砂）： 1277.9 m³

$$730.2 \times 1/0.90 = 811.3 \text{ m}^3$$

730.2
= 811.3
= 1277.9
0.0
- 0.0
+ 1277.9
0.0
土砂

床堀・埋戻

床堀（土砂）： m³

埋戻（土砂）： m³

$$0.0 - 0.0 \times 1/0.90 = 0.0 \text{ m}^3$$

盛 土

路床盛土（置換工）： 730.2 m³

盛土合計 730.2 m³

残 土

土 砂 1277.9 = 1277.9 m³

購 入 土

購 入 土 730.2 ÷ 0.9 = 811.3 m³
(地山土量)

AS舗装切断 数量計算書

測 点	距 離	舗装版切断 t=15cm以下					
				延長			
ST 300.0	-			4.8			
ST 320.0	20.0						
ST 330.0	10.0			2.1			
ST 340.0	10.0						
ST 360.0	20.0						
ST 380.0	20.0						
ST 390.0	10.0						
ST 400.0	20.0						
ST 420.0	20.0						
ST 440.0	20.0						
ST 460.0	20.0						
ST 480.0	20.0						
ST 500.0	20.0						
ST 520.0	20.0						
ST 540.0	20.0						
ST 560.0	20.0						
ST 566.0	6.0						
ST 580.0	14.0						
ST 584.0	4.0						
ST 600.0	16.0						
ST 620.0	20.0						
ST 635.0	15.0						
ST 637.0	2.0			2.1			
ST 640.0	3.0						
ST 656.0	16.0						
ST 660.0	4.0						
	-			5.0			
ST 680.0	20.0						
	-			10.0			
ST 700.0	20.0						
ST 720.0	20.0			4.0			
合 計				28.0			

既設AS舗装取壊し 数量計算書

種 別 番 号	距 離	既設舗装 t=5cm									摘 要
		W	平 均	数 量		平 均	数 量		平 均	数 量	
ST 300.0	-	4.80	-	-							
ST 320.0	20.0	3.90	4.35	87.0							
ST 330.0	10.0	4.00	3.95	39.5							
	-	6.10	-	-							
ST 340.0	10.0	5.30	5.70	57.0							
ST 360.0	20.0	4.50	4.90	98.0							
ST 380.0	20.0	6.50	5.50	110.0							
ST 390.0	10.0	5.40	5.95	59.5							
ST 400.0	10.0	3.80	4.60	46.0							
ST 420.0	20.0	3.30	3.55	71.0							
ST 440.0	20.0	4.00	3.65	73.0							
ST 460.0	20.0	4.00	4.00	80.0							
ST 480.0	20.0	3.90	3.95	79.0							
ST 500.0	20.0	4.00	3.95	79.0							
ST 520.0	20.0	4.60	4.30	86.0							
ST 540.0	20.0	3.90	4.25	85.0							
ST 560.0	20.0	3.50	3.70	74.0							
ST 566.0	6.0	4.00	3.75	22.5							
ST 580.0	14.0	5.40	4.70	65.8							
ST 584.0	4.0	6.50	5.95	23.8							
ST 600.0	16.0	5.00	5.75	92.0							
ST 620.0	20.0	4.30	4.65	93.0							
ST 635.0	15.0	6.00	5.15	77.3							
ST 637.0	2.0	6.00	6.00	12.0							
	-	8.10	-	-							
ST 640.0	3.0	8.20	8.15	24.5							
ST 656.0	16.0	5.30	6.75	108.0							
ST 660.0	4.0	4.90	5.10	20.4							
ST 680.0	20.0	4.00	4.45	89.0							
ST 700.0	20.0	4.10	4.05	81.0							
ST 720.0	20.0	4.00	4.05	81.0							
				m ²							
計				1,914.3							

土工 数量計算書

種 別 番 号	距 離	掘削工 (t=70cm)			置換工 (路床盛土)						摘 要
		W	平 均	数 量	W	平 均	数 量		平 均	数 量	
ST 300.0	-	4.40	-	-	4.40	-	-				
ST 320.0	20.0	3.80	4.10	82.0	3.80	4.10	82.0				
ST 330.0	10.0	3.50	3.65	36.5	3.50	3.65	36.5				
	-	5.60	-	-	5.60	-	-				
ST 340.0	10.0	5.00	5.30	53.0	5.00	5.30	53.0				
ST 360.0	20.0	4.30	4.65	93.0	4.30	4.65	93.0				
ST 380.0	20.0	5.80	5.05	101.0	5.80	5.05	101.0				
ST 390.0	10.0	5.20	5.50	55.0	5.20	5.50	55.0				
ST 400.0	10.0	3.60	4.40	44.0	3.60	4.40	44.0				
ST 420.0	20.0	3.20	3.40	68.0	3.20	3.40	68.0				
ST 440.0	20.0	3.80	3.50	70.0	3.80	3.50	70.0				
ST 460.0	20.0	3.60	3.70	74.0	3.60	3.70	74.0				
ST 480.0	20.0	3.60	3.60	72.0	3.60	3.60	72.0				
ST 500.0	20.0	3.80	3.70	74.0	3.80	3.70	74.0				
ST 520.0	20.0	4.20	4.00	80.0	4.20	4.00	80.0				
ST 540.0	20.0	3.70	3.95	79.0	3.70	3.95	79.0				
ST 560.0	20.0	3.70	3.70	74.0	3.70	3.70	74.0				
ST 566.0	6.0	3.70	3.70	22.2	3.70	3.70	22.2				
ST 580.0	14.0	5.40	4.55	63.7	5.40	4.55	63.7				
ST 584.0	4.0	6.50	5.95	23.8	6.50	5.95	23.8				
ST 600.0	16.0	5.30	5.90	94.4	5.30	5.90	94.4				
ST 620.0	20.0	4.00	4.65	93.0	4.00	4.65	93.0				
ST 635.0	15.0	5.50	4.75	71.3	5.50	4.75	71.3				
ST 637.0	2.0	5.60	5.55	11.1	5.60	5.55	11.1				
	-	8.10	-	-	8.10	-	-				
ST 640.0	3.0	8.00	8.05	24.2	8.00	8.05	24.2				
ST 656.0	16.0	4.80	6.40	102.4	4.80	6.40	102.4				
ST 660.0	4.0	4.70	4.75	19.0	4.70	4.75	19.0				
ST 680.0	20.0	4.00	4.35	87.0	4.00	4.35	87.0				
ST 700.0	20.0	4.00	4.00	80.0	4.00	4.00	80.0				
ST 720.0	20.0	3.80	3.90	78.0	3.80	3.90	78.0				
計				1,825.6	m2		1,825.6	m2			
			×0.7=	1,277.9	m3	×0.4=	730.2	m3			

路盤工 数量計算書

種 別 番 号	距 離	下層路盤工 (t=150mm)			上層路盤工 (t=150mm)			表層工 (t=50mm)			摘 要
		W3	平 均	数 量	W2	平 均	数 量	W1	平 均	数 量	
ST 300.0	-	4.40	-	-	4.40	-	-	4.40	-	-	
ST 320.0	20.0	3.80	4.10	82.0	3.80	4.10	82.0	3.80	4.10	82.0	
ST 330.0	10.0	3.50	3.65	36.5	3.50	3.65	36.5	3.50	3.65	36.5	
	-	5.60	-	-	5.60	-	-	5.60	-	-	
ST 340.0	10.0	5.00	5.30	53.0	5.00	5.30	53.0	5.00	5.30	53.0	
ST 360.0	20.0	4.30	4.65	93.0	4.30	4.65	93.0	4.30	4.65	93.0	
ST 380.0	20.0	5.80	5.05	101.0	5.80	5.05	101.0	5.80	5.05	101.0	
ST 390.0	10.0	5.20	5.50	55.0	5.20	5.50	55.0	5.20	5.50	55.0	
ST 400.0	10.0	3.60	4.40	44.0	3.60	4.40	44.0	3.60	4.40	44.0	
ST 420.0	20.0	3.20	3.40	68.0	3.20	3.40	68.0	3.20	3.40	68.0	
ST 440.0	20.0	3.80	3.50	70.0	3.80	3.50	70.0	3.80	3.50	70.0	
ST 460.0	20.0	3.60	3.70	74.0	3.60	3.70	74.0	3.60	3.70	74.0	
ST 480.0	20.0	3.60	3.60	72.0	3.60	3.60	72.0	3.60	3.60	72.0	
ST 500.0	20.0	3.80	3.70	74.0	3.80	3.70	74.0	3.80	3.70	74.0	
ST 520.0	20.0	4.20	4.00	80.0	4.20	4.00	80.0	4.20	4.00	80.0	
ST 540.0	20.0	3.70	3.95	79.0	3.70	3.95	79.0	3.70	3.95	79.0	
ST 560.0	20.0	3.70	3.70	74.0	3.70	3.70	74.0	3.70	3.70	74.0	
ST 566.0	6.0	3.70	3.70	22.2	3.70	3.70	22.2	3.70	3.70	22.2	
ST 580.0	14.0	5.40	4.55	63.7	5.40	4.55	63.7	5.40	4.55	63.7	
ST 584.0	4.0	6.50	5.95	23.8	6.50	5.95	23.8	6.50	5.95	23.8	
ST 600.0	16.0	5.30	5.90	94.4	5.30	5.90	94.4	5.30	5.90	94.4	
ST 620.0	20.0	4.00	4.65	93.0	4.00	4.65	93.0	4.00	4.65	93.0	
ST 635.0	15.0	5.50	4.75	71.3	5.50	4.75	71.3	5.50	4.75	71.3	
ST 637.0	2.0	5.60	5.55	11.1	5.60	5.55	11.1	5.60	5.55	11.1	
	-	8.10	-	-	8.10	-	-	8.10	-	-	
ST 640.0	3.0	8.00	8.05	24.2	8.00	8.05	24.2	8.00	8.05	24.2	
ST 656.0	16.0	4.80	6.40	102.4	4.80	6.40	102.4	4.80	6.40	102.4	
ST 660.0	4.0	4.70	4.75	19.0	4.70	4.75	19.0	4.70	4.75	19.0	
ST 680.0	20.0	4.00	4.35	87.0	4.00	4.35	87.0	4.00	4.35	87.0	
ST 700.0	20.0	4.00	4.00	80.0	4.00	4.00	80.0	4.00	4.00	80.0	
ST 720.0	20.0	3.80	3.90	78.0	3.80	3.90	78.0	3.80	3.90	78.0	
				m ²			m ²			m ²	
計				1,825.6			1,825.6			1,825.6	