

町道 赤羽根線
(竹迫宅 付近)

数 量 総 括 表

(1/2)

工 種	種 別	細 目	単位	計上過程の数値	設計計上数値	摘 要
土 工	掘 削	砂質土	m ³	12.3	10	計第 1 表
	盛土	路体盛土 (W<2.5)	m ³	1.2	1	計第 2 表
	残土処分		m ³	14.8	10	土量配分表
擁 壁 工	作業土工					
	床 掘	砂質土	m ³	13.5	10	計第 3 表
	埋 戻	砂質土	m ³	8.7	9	〃
	基面整正		m ²	8.2	---	〃
	コンクリート ブロック積	控え35cm 裏コン10cm	m ²	18.2	18	計第 4 表
	裏込碎石	裏込碎石 RC-40	m ³	4.8	5	〃
	ブロック基礎工	B520-H300	m	11.7	12	計第 4 表
	〃	コンクリート	m ³	1.140	---	設計図 (10m当り)
	〃	型 枠	m ²	4.000	---	〃
	〃	基礎碎石	m ²	7.200	---	〃
	天端コンクリート	コンクリート	m ³	1.4	1	計第 5-1.2 表
	〃	型 枠	m ²	4.5	---	〃
	小口止工	壁高=1.71m	箇所	(1.0)	(1)	設計図
	〃	コンクリート	m ³	0.365	---	〃
		型 枠	m ²	2.973	---	〃
	止水壁	コンクリート	m ³	0.137	0.1	設計図
	〃	型 枠	m ²	2.030	2.0	〃

町道 赤羽根線
(竹迫宅 付近)

数量総括表

(2/2)

[illegible]

土 工 配 分 表

〈 本 工 事 〉

掘 削

掘削工（土砂）：12.3 m³

$$\begin{array}{rcl} 1.2 & \times & 1/0.90 \\ = & 1.3 & \text{m}^3 \end{array}$$

盛 土

盛土：1.2 m³

床堀・埋戻

床堀（土砂）：13.5 m³

埋戻（土砂）：8.7 m³

$$\begin{array}{rcl} 13.5 & - & 8.7 \times 1/0.90 \\ = & 3.8 & \text{m}^3 \end{array}$$

14.8
=
1.3
-
12.3
+
3.8
土砂

残 土

土 砂 14.8 = 14.8 m³

盛土合計 1.2 m³

[illegible]

[illegible]

計 第 3 表					土 工				計 算 書			
測 点	床 堀				埋 戻				基面整正			
	距離(m)	断 面	平 均	立積(m³)	距離(m)	断 面	平 均	立積(m³)	距離(m)	巾	平 均	平積(m²)
SECT0.0		1.1				0.7				0.7		
SECT5.0	5.0	1.1	1.10	5.5	5.0	0.7	0.70	3.5	4.7	0.7	0.70	3.3
SECT12.0	7.0	1.1	1.10	7.7	7.0	0.7	0.70	4.9	7.0	0.7	0.70	4.9
止水壁箇所												
		0.2				0.2						
SECT0.0	1.3	0.2	0.20	0.3	1.3	0.2	0.20	0.3				

[illegible]

計 第 5-1 表 天端コンクリート (天端コンクリート) 計 算 書												
測 点	コンクリート				型 枠							
	距離(m)	断 面		立積(m³)	距離(m)	辺 長		平積(m²)	距離(m)		平 均	積
SECT0.0												
		0.0813				0.208						
SECT5.0	4.7	0.0813		0.382	4.7	0.208		0.978				
SECT12.0	7.0	0.0813		0.569	7.0	0.208		1.456				
計	11.7			0.951	11.7			2.434	0.0			0.0

計 第 5-2 表 天端コンクリート (調整コンクリート) 計 算 書												
測 点	コンクリート				型 枠							
	距離(m)	断 面		立積(m³)	距離(m)	辺 長		平積(m²)	距離(m)		平 均	積
SECT0.0												
		0.0405				0.180						
SECT5.0	4.7	0.0405		0.190	4.7	0.180		0.846				
SECT12.0	7.0	0.0405		0.284	7.0	0.180		1.260				
計	11.7			0.474	11.7			2.106	0.0			0.0

	コンクリート (m3)				型 枠 (m2)							
天端コ				0.951				2.434				
調整コ				0.474				2.106				
合計				1.4				4.5				0.0

[illegible]

計 第 7 表 取壊し工 計 算 書												
測 点	舗装剥取り				カッター切断工(AS)				コンクリート取壊し(既設止水壁)			
	距離(m)	巾	平 均	平積(m ²)	距離(m)	巾		延 長	距離(m)	断 面	平 均	立積(m ³)
SECT0.0		0.5				0.5		0.5				
SECT5.0	5.0	0.4	0.45	2.3	5.0			5.0				
SECT12.0	7.0	0.1	0.25	1.8	7.0	0.1		7.1				
SECT 6.4 付近		0.6				0.6		0.6				
SECT10.8 付近	4.4	0.6	0.60	2.6		0.6		0.6				
止水壁 箇所										0.1		
SECT0.0									1.3	0.1	0.10	0.13
合計	16.4			6.7				13.8				0.13

計 第 8 表 撤去・設置(延長調書) 計 算 書												
測 点	KF-250											
	距離(m)			延 長	距離(m)			延 長	距離(m)			延 長
SECT0.0												
	2.0			2.0								
合計				2.0								