

町道 青近3号線
(岡田宅 付近)

数 量 総 括 表

(1/2)

工 種	種 別	細 目	単位	計上過程の数値	設計計上数値	摘 要
土 工	掘 削 (A)	砂質土	m ³	133.4	130	計第 1 表
	盛 土	路床盛土 (W<2.5)	m ³	12.0	10	計第 2-2表
		路体盛土 (W<2.5)	m ³	11.5	10	〃 盛土、路肩盛土含む
	残土処分		m ³	115.7	120	土量配分表
植生工	盛土法面整形		m ²	26.9	30	計第 3 表
	人工張芝		m ²	26.9	30	〃
擁 壁 工	作業土工					
	床 掘	砂質土	m ³	24.0	20	計第 4 表
	埋 戻	砂質土	m ³	14.0	10	〃
	基面整正		m ²	15.6	---	〃
	コンクリート ブロック積	控え35cm 裏コン15cm	m ²	75.1	75	計第 5 表
	裏込碎石	裏込碎石 RC-40	m ³	30.7	31	〃
	ブロック基礎工	B550-H350	m	19.4	19	計第 5 表
	〃	コンクリート	m ³	1.363	---	設計図 (10m当り)
	〃	型 枠	m ²	4.50	---	〃
	〃	基礎碎石	m ²	7.50	---	〃
	天端コンクリート	コンクリート	m ³	2.9	3.0	計第 6-1.2 表
	〃	型 枠	m ²	9.0	---	〃
	1号小口止工	壁高=4.59m	箇所	(1.0)	(1)	設計図
		コンクリート	m ³	1.369	---	〃
		型 枠	m ²	10.652	---	〃
	2号小口止工	壁高=3.75m	箇所	(1.0)	(1)	設計図
		コンクリート	m ³	1.064	---	〃
		型 枠	m ²	8.334	---	〃
取付工	練石積	100%採取	m ²	14.6	15	計第 7 表

町道 青近3号線
(岡田宅 付近)

数 量 総 括 表

(2/2)

[illegible]

土 工 配 分 表

〈 本 工 事 〉

掘 削

掘削工 A (土砂) : 133.4 m³

$$\begin{array}{rcl} 23.5 & \times & 1/0.90 \\ = & 26.1 & \text{m}^3 \end{array}$$

$$\begin{array}{rcl} 8.4 & + & 133.4 \\ & - & 26.1 \\ \hline & = & 115.7 \end{array}$$

土砂

床堀・埋戻

床堀 (土砂) : 24.0 m³

埋戻 (土砂) : 14.0 m³

$$\begin{array}{rcl} 24.0 & - & 14.0 \\ & \times & 1/0.90 \\ \hline & = & 8.4 \text{ m}^3 \end{array}$$

盛 土

盛土 : 0.5 m³

路肩盛土 : 1.0 m³

路床盛土 (W<2.5) : 12.0 m³

路体盛土 (W<2.5) : 10.0 m³

盛土合計 23.5 m³

残 土

土 砂 115.7 = 115.7 m³

[illegible]

計 第 2-1 表					土 工				計 算 書			
測 点	盛土											
	距離(m)	断 面	平 均	立積(m³)	距離(m)			積	距離(m)		平 均	積
SECT0.0												
SECT12.0		0.0										
SECT20.0	8.0	0.1	0.05	0.4								
	2.4	0.0	0.05	0.1								
計	10.4			0.5	0.0			0.0	0.0			0.0

計 第 2-2 表					土 工				計 算 書			
測 点	路肩盛土				路床盛土 (W<2.5)				路体盛土 (W<2.5)			
	距離(m)	断 面	平 均	立積(m³)	距離(m)	断 面	平 均	立積(m³)	距離(m)	断 面	平 均	立積(m³)
SECT0.0		0.0				0.0				0.0		
SECT12.0	12.0	0.1	0.05	0.6	12.0	1.2	0.60	7.2	12.0	1.0	0.50	6.0
SECT20.0	8.0	0.0	0.05	0.4	8.0	0.0	0.60	4.8	8.0	0.0	0.50	4.0
計	20.0			1.0	20.0			12.0	20.0			10.0

計 第 3 表 植 生 工 計 算 書												
測 点	盛土法面整形				人工張芝				人工張芝			
	距離(m)	法 長	平 均	平積(m ²)	距離(m)	法 長	平 均	平積(m ²)	距離(m)	法 長	平 均	平積(m ²)
SECT0.0												
		0.0				0.0						
SECT12.0	11.1	1.9	0.95	10.5	11.1	1.9	0.95	10.5				
SECT20.0	8.0	1.7	1.80	14.4	8.0	1.7	1.80	14.4				
	2.4	0.0	0.85	2.0	2.4	0.0	0.85	2.0				
合計	21.5			26.9				26.9				0.0

計 第 4 表					土 工				計 算 書			
測 点	床 堀				埋 戻				基面整正			
	距離(m)	断 面	平 均	立積(m³)	距離(m)	断 面	平 均	立積(m³)	距離(m)	巾	平 均	平積(m²)
SECT0.0		1.2				0.7				0.8		
SECT12.0	12.0	1.2	1.20	14.4	12.0	0.7	0.70	8.4	11.7	0.8	0.80	9.4
SECT20.0	8.0	1.2	1.20	9.6	8.0	0.7	0.70	5.6	7.7	0.8	0.80	6.2

計第5表					コンクリートブロック積				計算書			
測点	SL 積ブロック				G 裏込材							
	距離	斜長	平均	平積(m ²)	距離	断面	平均	立積(m ³)			平均	積
SECT0.0												
		4.5				2.0						
SECT12.0	11.7	3.6	4.05	47.4	11.7	1.4	1.70	19.9				
	7.7	3.6	3.60	27.7	7.7	1.4	1.40	10.8				
SECT20.0												
合計	19.4			75.1	19.4			30.7	0.0			

計 第 6-1 表 天端コンクリート (天端コンクリート) 計 算 書												
測 点	コンクリート				型 枠							
	距離(m)	断 面	平均	立積(m³)	距離(m)	辺 長	平均	平積(m²)	距離(m)		平 均	積
SECT0.0												
		0.0792				0.212						
SECT12.0	11.7	0.0899	0.08455	0.989	11.7	0.212	0.2120	2.480				
	7.7	0.0899	0.08990	0.692	7.7	0.212	0.2120	1.632				
SECT20.0												
計	19.4			1.681	19.4			4.112	0.0			0.0

計 第 6-2 表 天端コンクリート (調整コンクリート) 計 算 書												
測 点	コンクリート				型 枠							
	距離(m)	断 面		立積(m³)	距離(m)	辺 長		平積(m²)	距離(m)		平 均	積
SECT0.0												
		0.0625				0.250						
SECT12.0	11.7	0.0625		0.731	11.7	0.250		2.925				
	7.7	0.0625		0.481	7.7	0.250		1.925				
SECT20.0												
計	19.4			1.212	19.4			4.850	0.0			0.0

	コンクリート (m3)				型 枠 (m2)							
天端コン				1.681				4.112				
調整コン				1.212				4.850				
合計				2.9				9.0				0.0

[illegible]

[illegible]

[illegible]